

# **ADDENDUM NO. 1**

## **VILLAGE OF NEW BREMEN First Street Reconstruction**

**April 8, 2015**

To: Planholders

From: Mote & Associates, Inc.  
214 West Fourth Street  
Greenville, Ohio 45331  
Phone: (937) 548-7511  
Fax: (937) 548-7484  
E-mail: info@moteassociates.com

Re: Village of New Bremen  
First Street Reconstruction

This addendum forms a part of the Contract Documents and modifies the original Contract Documents dated March 2015. Acknowledge receipt of this Addendum in the space provided on the Bid Proposal form. Failure to do so may subject the Bidder to disqualification.

### **CHANGES/CLARIFICATIONS TO THE CONTRACT DOCUMENTS:**

1. Advertisement for Bids 00 11 13 and Instructions to Bidders 00 21 13
  - The completion date for the project has been modified. All portions of the project on First Street located between S.R. 66 through the intersection of Walnut Street shall be completed by August 14, 2015 so that there will not be any interruption to the ABC Center's school operation as they open for the new year. The remainder of the project shall be completed thereafter, but no later than October 2, 2015.

### **CHANGES/CLARIFICATIONS TO THE CONSTRUCTION PLANS**

2. Construction Drawings - Sheet #5 of 16
  - The following addition shall be added to note #13, Item 611 Storm Sewer (ODOT 707.13):  
  
*Preparation of an Installation Plan, Performance Inspection requirements, and conduit and drainage structure evaluations (ODOT CMS sections 611.04, 611.12, 611.13, and 611.14) are not required for this project. All storm sewer and waterline shall be constructed in accordance with the "Trench Backfill Detail" found on sheet 2 of 16.*
3. Construction Drawings - Sheet #5 of 16

- The following modification shall be made to the third sentence in note #34, Proposed Storm Drains:

*The storm drain shall be extended to the location shown, an 8" x 8" tee installed with an 8" cap placed on the horizontal end of the tee and an 8" extension installed from the vertical end of the tee to a point flush with the finish grade elevation and capped.*

Please note that the quantities provided on the plans and the proposal include the proper fittings although the note had not been modified.

End of Addendum