

ADDENDUM NO. 2

VILLAGE OF PHILLIPSBURG State Street Improvements Phase I (Rebid) September 1, 2016

To: Planholders

From: Mote & Associates, Inc.
214 West Fourth Street
Greenville, Ohio 45331

Phone: (937) 548-7511
Fax: (937) 548-7484
E-mail: info@moteassociates.com

Re: Village of Phillipsburg
State Street Improvements Phase I

This Addendum forms a part of the Contract Documents and modifies the original Contract Documents dated August 2016. Acknowledge receipt of this Addendum in the space provided on the Bid Proposal form. Failure to do so may subject the Bidder to disqualification.

CHANGES / CLARIFICATIONS TO THE DETAIL CONSTRUCTION PLANS:

1. The following paragraph shall be added to Note #12 on Sheet #6/16 of the plans:

“PREPARATION OF INSTALLATION PLAN, PERFORMANCE INSPECTION REQUIREMENTS, AND CONDUIT AND DRAINAGE STRUCTURE EVALUATIONS (ODOT CMS SECTIONS 611.04, 611.12, 611.13 AND 611.14) ARE NOT REQUIRED FOR THIS PROJECT. ALL STORM SEWER SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE "SEWER TRENCH BACKFILL DETAIL" FOUND ON SHEET #3/16.”

GENERAL CLARIFICATIONS:

2. As a follow-up to the Pre-Bid Meeting, a portion of the work can be accomplished with one lane closed. The Contractor will be responsible for all flagging. Portable solar stoplights will be acceptable for use in lieu of flagmen.
3. The street will need closure with a detour approved by ODOT for part of the work. A maximum of 60 days may be requested for a full road closure. The Village would like to minimize this time as much as possible.
4. Rock is not anticipated to be a problem with the infrastructure construction. When the sanitary force main was installed within the project limits, some “weathered rock” was encountered in the bottom of the trench in some areas and was able to be excavated. If unexcavatable rock is encountered, a rock excavation unit price will be negotiated.
5. A Pre-Bid Meeting was held on August 31, 2016. The notes and sign-in sheet are attached to this Addendum #2.

End of Addendum

Attachments: Pre-Bid Meeting Notes and Sign-in Sheet



“Serving your engineering and surveying needs since 1972”

**S. STATE ST. IMPROVEMENTS
VILLAGE OF PHILLIPSBURG**

PRE-BID MEETING NOTES –AUGUST 31, 2016

- Project owner is Village of Phillipsburg with funding from Ohio Public Works Commission and local funds. Montgomery County has no involvement. Detours will be coordinated with ODOT since State St. is also SR 49.
- The project is being re-bid since no awardable bids were received at the bid opening on August 2, 2016.
- The completion date has been extended to June 30, 2017. However, any construction initiated this fall must be completed in such a manner that the trenches can be restored as required before the asphalt companies close for the winter. No trenches will be permitted to be left unpaved over the winter. This is a Village requirement. Construction does not have to start this fall.
- Sidewalk has been shown as an alternate bid.
- A detour map has been added for the contractor’s reference. The contractor will be responsible for all detour signage during any road closures.
- The Engineer’s Construction Estimate has been revised and is listed in article 26.01 of the Contract Documents.
- ODOT plans to resurface SR 49 in Phillipsburg in 2017 after this project is completed.
- Maintenance of Traffic notes currently do not specify a maximum time for a road closure with detour. Engineer will address in addendum. Flagging during one lane closures will be the responsibility of the contractor. The Village stressed the desire to keep trucks on the specified detour whenever in effect.
- Rock is not anticipated to be a problem with the project. This subject will be addressed more in the addendum.
- The asphalt concrete quantities listed on the bid form were calculated for the pavement replacement area in front of the new curb and gutter.
- Asphalt quantities needed for trench restoration shall be included in the unit price bid for the respective conduit (see note under the “Storm Sewer Trench Backfill Detail” on sheet 3/16).
- Curb boxes were added to the detail for the water services on sheet 5/16 as part of the rebid changes.
- Vectren is finishing installation of a new gas line within the project limits. They may need to finish some service lines while this project is under construction. Coordination will be addressed at the preconstruction conference.
- Item 611 note on the General Notes sheet should have specified ODOT requirements that are not needed with this project. This note will be added in the addendum.

End of Notes

214 West Fourth Street, Greenville, Ohio 45331 • (937) 548-7511 • Fax: (937) 548-7484

E-mail: info@moteassociates.com • Web: www.moteassociates.com

"Serving your engineering and surveying needs since 1972"

VILLAGE OF PHILLIPSBURG
S. State Street Reconstruction
Bid Opening - Thursday, Sept. 8, 2016 @ 11:00 A.M.

Engineer's Estimate: Base Bid =\$546,100
Alternate Bid #1 =\$ 82,703
Alternate Bid #2 =\$ 23,322

PRE-BID MEETING SIGN-IN SHEET

	<u>REPRESENTATIVE'S NAME</u>	<u>NAME OF COMPANY</u>
1.	Jerry McClannan	Mote & Associates
2.	Sheryl Riffell	P-burg Council
3.	Cheryl Crabtree	Mayor - Phillipsburg
4.	Wendell Harlemaas	Street Dept Phillipsburg
5.	Jacob Waterman	UTF Excavation
6.	DAN HAYES	BRUNBAUGH
7.	SEAN WADE	EAGLE BRIDGE
8.	Kipp Boone	Belgray Inc
9.		
10.		
11.		
12.		
13.		
14.		
15.		

214 West Fourth Street, Greenville, Ohio 45331 • (937) 548-7511 • Fax: (937) 548-7484