

# ADDENDUM NO. 3 - REBID

## VILLAGE OF WEST MANSFIELD Water Treatment Plant Shop & Lime Sludge Dewatering Building

February 16, 2015

To: Planholders

From: Mote & Associates, Inc.  
214 West Fourth Street  
Greenville, Ohio 45331  
Phone: (937) 548-7511  
Fax: (937) 548-7484  
E-mail: info@moteassociates.com

Re: Village of West Mansfield  
Water Treatment Plant Shop & Lime Sludge Dewatering Building

This addendum forms a part of the Contract Documents and modifies the original Contract Documents dated January 2015. Acknowledge receipt of all Addenda in the space provided on the Bid Proposal form. Failure to do so may subject the Bidder to disqualification.

### CHANGES/CLARIFICATIONS TO THE BIDDING REQUIREMENTS AND DRAWINGS:

1. Sheet Metal Roofing, Ceiling, and Wall Clarifications
  - A. Standing Seam Sheet Metal Roofing: Premium Pro-Snap concealed-fastener, 28-gauge roofing panel by Midwest Manufacturing is an acceptable material for the standing seam sheet metal roof. The G-100 galvanized plus zinc phosphate coating and the standard manufacturer's warranty are both acceptable.
  - B. Sheet Metal Wall and Ceiling Panels: Premium Pro-Rib exposed-fastener, 28-gauge panel by Midwest Manufacturing is an acceptable material for the interior and exterior wall panels and the interior ceiling panels. The G-100 galvanized plus zinc phosphate coating and the standard manufacturer's warranty are both acceptable.
2. Sheet #13 of 14, Sludge Dewatering System Sections
  - A. Sheet Note #1 Clarification, Peristaltic Pump Startup and Training: No startup and training is required for the peristaltic pump itself due to owner familiarity with the specified pump. Startup and training is required for the dewatering system as a whole, though, as described.

End of Addendum