

ADDENDUM NO. 1

VILLAGE OF NEW MADISON North Main Street Sidewalk Replacement May 15, 2018

To: Planholders

From: Mote & Associates, Inc. Phone: (937) 548-7511
214 West Fourth Street Fax: (937) 548-7484
Greenville, Ohio 45331 E-mail: info@moteassociates.com

Re: Village of New Madison
North Main Street Sidewalk Replacement

This Addendum forms a part of the Contract Documents and modifies the original Contract Documents dated April, 2018. Acknowledge receipt of this Addendum in the space provided on the Bid Proposal form. Failure to do so may subject the Bidder to disqualification.

CHANGES/CLARIFICATIONS TO THE CONSTRUCTION PLANS:

1. PLAN SHEET #3 of 4

Additional notes regarding adjacent appurtenances to the sidewalk shown on Sheet #3 of 4 are as follows based on the street address:

- a) 112 N. Main Street – Existing bush shown “to be removed” has already been removed.
- b) 120 N. Main Street – Saw cut existing sidewalk joint 18” left.
- c) 130 N. Main Street – Remove and replace existing steps. Work will be measured and quantity added to Item 202 Step Removed and Item 608 Concrete Step for payment.
- d) 136 N. Main Street – Install 5/4 treated form board between stone retaining wall and proposed sidewalk. Fill void spaces with sand.
- e) 202 N. Main Street – Replace service walks as needed on both sides of house to match up to existing. Cost of service walks will be measured and added to Item 608, Concrete Walk, as per plan, at completion of project. Existing hedge noted on plans “to be removed” has already been removed.

Any cost for the incidental items listed above shall be included in the cost of Item 608, Concrete Walk, as per plan, unless noted otherwise.

2. PLAN SHEET #4 of 4

Additional notes regarding adjacent appurtenances to the sidewalk to be replaced are as follows based on the street address:

- a) 230 N. Main Street – Remove existing railroad ties and grade to walk or remove and re-set as per Owner.
- b) 238 N. Main Street – Replace service walk between back of sidewalk and steps. Cost of service walk will be measured and added to Item 608, Concrete Walk, as per plan, at completion of project.

- c) 264 N. Main Street – Remove brick walk and edge, then grade with topsoil to new walk.
- d) 270 N. Main Street – Replace service walk between new sidewalk and house. Cost of service walk will be measured and added to Item 608, Concrete Walk, as per plan, at completion of project.
- e) 288 N. Main Street – Remove existing railroad ties and grade to walk.
- f) 294 N. Main Street – Remove existing railroad ties and grade to walk.
- g) Approximate Station 56+75 – Tree roots remain under sidewalk and will need removed to install new sidewalk.

Any cost for the incidental items listed above shall be included in the cost of Item 608, Concrete Walk, as per plan, unless noted otherwise.

GENERAL CLARIFICATIONS

- 3. Install ½” expansion joint material between sidewalk and all adjacent concrete appurtenances, including retaining walls. Expansion joint material shall be vinyl like Proflex as manufactured by Oscoda Plastics, Inc.
- 4. At all disturbed areas behind the sidewalk and in the tree lawn, place top soil to the elevation of the sidewalk/curb along with final grading prior to seeding and mulching.

End of Addendum