

ADDENDUM NO. 3

PALESTINE-HOLLANSBURG JOINT SEWER DISTRICT Centralized Wastewater System – Wastewater Treatment Facility September 2, 2021

To: Planholders

From: Mote & Associates, Inc. Phone: (937) 548-7511
214 West Fourth Street Fax: (937) 548-7484
Greenville, Ohio 45331 E-mail: info@moteassociates.com

Re: Palestine-Hollansburg Joint Sewer District
Centralized Wastewater System

This Addendum forms a part of the Contract Documents and modifies the original Contract Documents dated August 2021, Addendum #1 dated 08/18/21, and Addendum #2 dated 08/30/21. Acknowledge receipt of this Addendum in the space provided on the Bid Proposal Form. Failure to do so may subject the Bidder to disqualification.

CHANGES/CLARIFICATIONS TO THE CONTRACTING DOCUMENTS:

1. INSTRUCTIONS TO BIDDERS, SECTION 00 21 13

Article 26 – Engineer’s Estimate has been revised for Contract ‘B’ – Wastewater Treatment Facility from \$2,600,000 to \$3,200,000.

CHANGES/CLARIFICATIONS TO THE TECHNICAL SPECIFICATIONS:

2. CHAIN LINK FENCE AND GATES, SECTION 32 31 13

A. Section 1.01, Work Included shall be revised to reflect the following gates for the perimeter fence located at the Wastewater Treatment Plant:

One – 20’ double swing gate at entrance (double 10’ gates)
Two – 4’ pedestrian gates

B. Section 2.03, End, Corner and Pull Posts, the first item listed shall be changed to:

ODOT 710.03, Grade 2 pipe – OD 4”

C. Section 3.03, Fence Installation, Item A. shall state: Posts shall include footers for the line post that shall be a minimum 12” diameter and 36” deep with the top of the concrete to grade elevation. The footings for the terminal posts shall be a minimum of 12” diameter and 42” deep with the top of the concrete to grade elevation. This is in lieu of the five foot (5’) deep footers shown on the Security Fencing Details on Sheet 6 of 8 of the General Details.

END OF ADDENDUM