

ADDENDUM NO. 2

**WEST MANCHESTER FIRE DEPARTMENT
PREBLE COUNTY, OHIO
NEW TRUCK BAY FACILITY**

January 27, 2025

To: Planholders

From: Mote & Associates, Inc.
214 West Fourth Street
Greenville, Ohio 45331
Phone: (937) 548-7511
Fax: (937) 548-7484

Re: West Manchester Fire Department
New Truck Bay Facility

This addendum forms a part of the Contract Documents and modifies the original Contract Documents dated January 2025. Acknowledge receipt of this Addendum in the space provided on the Bid Proposal form. Failure to do so may subject the Bidder to disqualification.

CLARIFICATIONS / REVISIONS / ADDITIONS TO PLAN SHEETS:

1. Sheet G1-01 – Add the following text to the existing text of keynote #7 “The precast concrete vault shall be constructed to accommodate the necessary depth of the oil interceptor and associated piping, shall meet ODOT 706.13 requirements for precast concrete structures with a pedestrian traffic rated access hatch that will accommodate the maintenance and removal of the oil interceptor unit without disassembly.”
2. Sheet P1-01 – In the plumbing fixture schedule, the item Mark TD-1 and under the column Min Drain Size delete the text “4”x24’-7”” and replace with “6” wide X 10’-0” long with 4” discharge.”
3. Sheet P1-01 – In the plumbing fixture schedule, the item Mark OT-1 and under the column Description add the text “Like a Zurn Z1186-ST-500 or approved equal anchored to the precast concrete vault floor.” To the existing text.
4. Sheet E1-01 – In the light fixture schedule, the item Mark A and under the column Manufacturer/Model delete the text “Corelite D3X-WO-55L LED” and replace with “Metalux OHBL-12-SE-MCL-UNIV-L950-5LTDC3-U or approved equal.”

End of Addendum